WIRE DRAG

Diagram No. 1212-2

NOAA FORM 76-35A

U.S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SERVICE

DESCRIPTIVE REPORT

Type of Survey Wire Drag & Side Scan Sonar

Field No. R/H-20-11-83-R/H-20-13-83/84

Registery No. FE-257WD

LOCALITY

State ... New York

General Locality Long Island Sound

Sublocality ... Southeast of Sixmile Reef

19 83-84

CHIEF OF PARTY

LCDR D.D. Winter & LCDR R. K. Norris

LIBRARY & ARCHIVES

DATE July 17, 1985

☆U.S. GOV. PRINTING OFFICE: 1985-566-054

area 1

12358 to sign off see 123545 Record of Explications

AACS	FORM	77-28
111 - 7	21	

U.S. DEPARTMENT OF COMMERCE

RIGISTER NO.

HYDROGRAPHIC TITLE SHEET

FE-257WD

R/H 20-11-83

INSTRUCTIONS - The Hydrographic Sheet should be accompanied by this form, filled in as completely as possible, when the sheet is forwarded to the Office.

FIELD NO.

*		
*	StateNEW YORK	
7	General locality LONG ISLAND SOUND	
	Locality AWOIS #02729 AND AWOIS #02730 Southeast of Sixmile Reef	
	Scale 1:20,000 Date of survey 24 AUGUST 1983 Instructions dated 22 JULY 1983 Project No. OPR-B660-RU/HE-83	
	Instructions dated 22 JULY 1983 Project No. OPR-B660-RU/HE-83	
	Vessel_NOAA SHIPS RUDE (9040) AND HECK (9140)	
	Chief of party LCDR D. D. WINTER	
	Surveyed by LCDR D.D. WINTER, LT N.G. MILLETT, LT E.M. CLARK, ENS T.G. CALLAHAN	-
	Soundings taken by echo sounder, hand lead, pole ECHO SOUNDER, Side Scan Sonor, Wire Drag	-
	Graphic record scaled by ENS T.G. CALLAHAN, G.L. ANDERSEN	
	Graphic record checked by ENS T.G. CALLAHAN, G.L. ANDERSEN	
	Protracted by N/A Automated plot by N/A	
	Verification by Hydrographic Surveys Branch, Evaluation and Analysis Group, A.M.C. MLLW Soundings in freehomsx feet at MLW MKXV FOR PREDICTED TIDES Smooth Tides Applied	-
	REMARKS: ALL TIMES RECORDED IN UTC	
3 16-		
	AWOIS and SURF RUD 5/87	




TABLE OF CONTENTS

		OROGRAPHIC TITLE SHEET	
	PKL	GRESS SKETCH	11
	H.	PROJECT AUTHORITY	1
	D.	CHARACTERISTICS AND LIMITS OF SURVEY	1
	D.	SURVEY VESSELS	1
		HYDROGRAPHIC SHEETS	
		EQUIPMENT AND TECHNIQUES	
		CONTROL STATIONS	
			3
		DATES OF SURVEY	
		JUNCTIONS AND SPLITS	4
		COMPARISON WITH PRIOR SURVEY	4 5
		COMPARISON WITH THE CHARTS	
		ADEQUACY OF SURVEY	5
		INCOMPLETE ITEMS	5
		PERSONNEL	5
		GENERAL NOTES	
	CC.	DENEMAL MOJES	-
	APF	PENDICES	
*	A.	ABSTRACT OF ELECTRONIC CORRECTORS	- 1
		ABSTRACT OF DAILY STATISTICS	
	C.	HORIZONTAL CONTROL	9-14
		SIGNAL LIST	
			1-18
			1-19
K	G.	SHEET PARAMETERS	1-20
	H.	LOCAL NOTICE TO MARINERS REPORT	-22
		SMOOTH TIDE REQUEST - FIELD TIDE NOTE	
			-26
		TRANSMITTAL LETTERS	-27
*	L.	SETTLEMENT AND SQUAT DATA GEOGRAPHIC NAMES LIST (Field)	-37
*	M.	GEOGRAPHIC NAMES LIST (Field)	-40

* Data removed from the Descriptive Report and filed with the field records.

DESCRIPTIVE REPORT TO ACCOMPANY
HYDROGRAPHIC SURVEY **FE-257 **P** R/H 20-11-83
1:20,000 SCALE, 1983
NOAA SHIPS RUDE & HECK
LCDR DONALD D. WINTER, COMBG.

A. Project Authority

This project was conducted in accordance with Hydrographic Project Instructions OPR-B660-RU/HE-83, Southern New England Coast, dated 17 June 1983. Two amendments to the project instructions were Chanse No. 1 dated 22 July, 1983 and Chanse No. 2 dated 8 December, 1983. The purpose of this project was to verify or disprove certain reported submersed wrecks along the south coast of New England, to provide clearance depths over selected wreck sites, and to provide wire-drag clearance of the Northville Industries Corporation oil tanker route.

B. Characteristics and Limits of Area Surveyed

This report contains two ship wire dras strips, each .5 nautical miles wide and with a combined lineal distance of 3.21 nautical miles.

Ship wire dras strip O1 of JD 236 was conducted to clear the contact at the position latitude 41-10-29.52N., lonsitude O72-25-34.4W., protrudins 8.0 feet off the bottom in 136 feet of water. The contact was suspected to be the wreckase of the Barateria, which was classified as No. 01813 on the AWOIS listing for (1982) and renumbered (July 20, 1983) AWOIS NO. 02730.

The contact at latitude 41-09-19.25N., lonsitude 072-25-04.09W, which protrudes 9.5 feet off the bottom in 131 feet of water was cleared by ship wire dras on strip 03 of JD 236. The contact at this position was most probably that of the Thames, (1982) AWOIS No. 01814, which was renumbered (July 20,1983) AWOIS No. 02729. Stop A-2 (02 of JD 236) was rejected due to excessive lifts.

C. Survey Vessels

The NOAA Ships Rude (vesno 9040) and Heck (vesno 9140) conducted the wire dras for this survey .

D. Hydrographic Sheets

The Anydrosraphic sheets used in this survey were made of mylar and were constructed with the Disital PDP 11/34 computer and Houston Instrument roll-bed plotter aboard the NOAA Ship Rude. Four copies of field sheet R/H 20-11-83 were plotted at a scale of 1:20,000. Two copies of the field sheet are titled R/H 20-11A-83 and contain the hand plots of the vessel's positions taken while on line during the wire drag operations on JD 236. Two smooth field sheets were plotted aboard the Rude while on line using the same equipment as described above. Field sheet R/H 20-11B-83 depicts the area covered by wire drag operations on AWOIS # 02729, drag strip JD 236-01. Drag strip JD 236-03 was

Computer plotted on smooth field sheet R/H 20-11C-83 for AWOIS No. 02730. Dras strip 02 was not plotted or used because the strip was run asainst the tidal currents at depth, resultins in excessive lifts. The field records are being fowarded to the Atlantic Marine Center for verification and smooth plottins.

E. Equipment and Techniques

The ship wire dras operations were conducted usins standard wire dras equipment and techniques at effective depths greater than 70 feet. Numerous lobster pots were encountered in the survey area. The launches were used to test the drass and the drass were tested often.

Ship wire dras operations utilized five (5) intermediate and two (2) end buoys with 600 foot sections. The dras uprights were set to obtain effective depths sreater than 70 feet. The ship wire dras conducted for the AWOIS item No. 02729 developed effective depths of 75 feet. The wire dras operation for AWOIS No. 02730 established an effective depth of 79 feet. Both drass were run in one direction with the prevailing tidal currents, at depth, while maintaining a predetermined track line.

Del Norte rates obtained on fixes were recorded with Eaton Model 7000+ serial printers during this survey. These printers worked fairly well considering the fact that they were not designed to be operated in a marine environment. The printers would often print out a line of meaningless characters or rates from the previous fix before the current fix was recorded. The records were annotated such that these meaningless characters and extraneous rates were lined out leaving the corrected fix rates clearly displayed.

A Raytheon model DE-719B echo sounder, serial no. was operated and annotated during drag operations on the Heck for wire dras strip 03. Although it is not anticipated that these sounding records will be used for charting purposes, thev settlement and squat data for the Rude and Heck, obtained in Norfolk Harbor on 25 January 1983, is included in this report. No velocity corrections or settlement and squat determinations were actually conducted within or during this project.

The pre-survey depth data for these items, AWOIS No. 02729 protrudins 9.5 feet off the bottom in 131 feet of water and 02730 protrudins 8.0 feet in 136 feet of water, AWOIS No. indicated that divins operations were prohibitive due excessive depth. The soundings recorded were apparently not plotted by the field and no automated tapes of these soundings were submitted, therefore no plot of these soundings is available. The soundings collected are of reconnaissance value only and not intended for charting.

Two electronic control stations were used for this Staion 01 was established at an elevation of 28.6 meters on FALKNER ISLAND LIGHTHOUSE (1882), latitude 41-12-42.701N., lonsitude 072-39-14.608W. Station 02 was located at SAYBROOK LIGHTHOUSE (1861), with an elevation of 21.6 meters at latitude 41-16-16.894N., lonsitude 072-20-37.01%. These NGS monumented stations are Third-Order, Class I control accuracy. The station Positions are based upon the North American Datum of 1927.

G. Calibration and Positionins Control

Vessel positioning for all work was accomplished with the Del Norte 520 series electronic positioning equipment operated at a frequency of 9400 MHz in the range-range mode. A listing of DMU and master units used by the vessels during this survey are listed by Julian day in Appendix A. The remote installed at Station 01 was code 74, serial number 3003. Remote code, 76, serial number 3004 was installed at Station 02.

Two baseline calibrations were performed during this survey. All baseline calibrations were conducted in the immediate work area and entirely over water in accordance with AMC OPORDER 79. Baseline calibration distances were determined by the HP 3800A electronic distance measuring instrument, serial number 0987A00157. The following is a list of the baseline calibrations, as measured by the HP 3800A:

July, 1983 208	Belle Terre Beach Port Jefferson W.	2601.1 m
Ausust, 1983 239	Belle Terre Beach Port Jefferson W.	2601.1 m

The opening and closing calibrations for this one day operation were conducted using 3-point sextant fixes with check angles as follows: left object 14, KELSEY POINT BREAKWATER LT. (1934); center object 13, DUCK IS. WEST BREAKWATER LT. (1934); right object 16, LIBBY'S CHIMMEY (1934); and check object 12, DUCK IS. NORTH BREAKWATER LT. (1934). These objects are fully described in Appendix D. The daily mean corrector was within accuracy tolerances for a survey of this scale. Therefore, only the baseline calibration data should be applied to the raw position data during final processing. See Appendix A. for daily and baseline calibration data.

H. Dates of Survey

This survey was carried out on 24 August, 1983, JD 236.

I. Reduction and Processins of Data

The data collected during ship wire drag operations was manually entered in the wire drag volumes while on line. The position data was also entered into the Digital PDP 11/34 computer while on line. The program used was the R/H Double Precision Wire Drag program (1983). The drag strips were then smooth plotted with the Houston Instrument roll-bed plotter. Effective depths from the reduced data were then drawn on the drag strips. The drag strip data for strips 01 and 03 was then applied to the smooth field sheets R/H 20-11B-83 and R/H 20-11C-83.

Test data was applied to the drass in a method which differs slishtly from the Wire- Dras Manual. This method has been used aboard the dras boats for the past several years and was a more conservative method. When an uprisht was lowered, the deeper

dras depth was not claimed until the time of the first test at that depth. When an uprisht was raised, the dras depth from the previous test, after the raisins of the uprisht, was applied to the time when the uprisht was raised. If the amount of lift increased durins a dras, when uprishts remained unchansed, this decreased dras depth was applied back to a time halfway between the time of the sreater lift. Predicted tide correctors were then applied to the dras depths obtained from the application of the test data. The predicted tide correctors were senerated onboard the Rude with the ship's Disital PDP 11/34 computer and predicted tide tapes for 1983. These tide tapes were supplied to the ships by MOA 231. Hardcopy printouts of the predicted tide correctors used durins this survey are included in the data files. Lifts were recomputed during verification in accordance with the white Drey Manual Lifts and tide correctors were applied to the wire drey stryps of a secondance with the white Drey Manual during verification.

These wire dras surveys were item investigations with no junctions required.

K. Comparison with Prior Survey - See section 6.a. \$ 6.b. of the Evaluation Report.

Effective depths from the ship wire dras surveys were compared with the prior survey H-9181 (1970). This comparison was made using the prior survey of H-9181 (1970), which was included in the project instructions, at a scale of 1:20,000. The field sheets R/H 20-11B-83 and R/H 20-11C-83 were plotted at a scale of 1:20,000 and overlayed on the prior survey with direct comparison made. The charted soundings of H-9181 (1970) were greater than the effective depths of drag strip JD 236-01 and JD 236-03 and ranged from 79 feet to 173 feet in the common areas surveyed.

Soundings from field sheet R/H 20-11A-83 were also compared with the prior survey of H-9181. Only a crude comparison of soundings could be made with H-9181 since no velocity correctors were determined. Five soundings which differ with the prior survey are:

As previously stated in section E. Location	of this report, no field plat of the Surveyed Depth	Prior Survey Depth
→ 41-10-15.0N • 072-26-37.8W	119 feet	129 feet
^ 41-10-37.2N Ø 072-25-50.4W	114 "	118 "
³ 41-10-50.8N 4072-25-23.4W	109 e	117 "
* 41-11-06.0N • 072-24-59.4W	77 "	69 "
→ 41-11-09.0N ◆072-24-53.4W	77 .,	73 "

Differences noted were in the area of sand wave bottom topography. Sand waves are dynamic in nature and chanse with each

storm cycle. Thus with each storm cycle, the soundings would change in the sand wave area. - Concur

L. Comparison with Chart - See section 7. a. of the Evaluation Report.

The area surveyed is covered by (2) two NOS charts: 12354 25th Ed., July 31/82 and 12358 14th Ed., July 10/82. Landmarks inshore of the area wire drassed were visually verified from offshore and are suitable for chartins.

A number of floatins aids were charted in the vicinity of the area surveyed. For the surveyed positions of the floating aids to navisation, see Descriptive Report to Accompany Hydrographic Survey RU/HE-20-13-83 = included in this survey - FE-257WD

The positions of AWOIS No.02729 and 02730 are in agreement with the SUMMARY of CORRECTIONS, CHARTS OCTOBER 1983-VOLUME 1, EAST COAST OF NORTH AND SOUTH AMERICA (SUBREGIONS 11 THRU 15 AND 23 THRU 28), Subresion 12 page 12-91 for chart 12354. No conflicts exist between charted hydrography and present effective depths.

M. Adequacy of Survey

This survey completely covers AWOIS No. 02729 and AWOIS No. 02730. The depth of the contacts prohibited divins operations on these unidentified contacts. At the time of the survey sufficent upright wire was not available to hans contacts at the depths indicated in the AWOIS descriptions.

However, effective depths sreater than 70 feet have been cleared in one direction over the two positions in accordance with the project instructions for OPR-B660-RU/HE-83 and the Survey Requirements for AWOIS items No. 02729 and No. 02730 (20 July, 1983).

Descriptive Report to Accompany Hydrographic Survey RU/HE 20-13-83 covered the same area as AWOIS No. 02729 and field sheet R/H -20-11B-83.

As a result of these combined field sheets (R/H-20-11-82 & R/H-20-13-85/K4) AWOIS Item 2729 has been cleared in two directions to a minimum depth of 73 text, AWOIS Item 2730 remains cleared in only one direction. See sections 4. \$ 7. of

the Evaluation Report.

There were no incomplete items left on this survey.

O. Currents and Winds

In seneral, the surface and bottom tidal currents appeared to exhibit the same seneral characteristics and trends as observed in the vicinity of the Northville Oil Terminal. A complete description of these conditions is available in the Descriptive Report to Accompany Hydrosraphic Survey R/H 05-01/03-83 and R/H 10-02-83.

P. Personnel

The officers participating in this survey were LCDR Donald D. Winter, LT Neal G. Millett, LT Edward M. Clark and ENS Thomas G. Callahan.

Q. General Notes

See the Coast Pilot Report and the Loran-C comparisons for OPR-B660-RU/HE-83 and the Descriptive Report for OPR-B660-RU/HE-82 for additional information on this survey.

The format of this report is a composite of the Descriptive Report formats contained in the Wire Dras and Hydrographic Manuals. This format is the optimum composite of the pertinent sections of the two reports and is more applicable to the surveys currently being conducted by the Rude and Heck: Concur

Respectively submitted,

Schward M. Clark, LT, NOAA

APPROVAL SHEET

R/H 20-11-83

· Field operations contributing to the accomplishemnt of this survey were conducted under my supervision with frequent personal checks of progress and adequacy. This report and field sheets have been closely reviewed and are considered complete and adequate for charting.

TCDB MOYY

LCDR, NOAA

Commanding Officer

NOAA Ships RUDE & HECK

C. HORIZONTAL CONTROL

No new stations were established for this survey. See Appendix D., Signal List for a complete listing of all stations used on this survey

D. SIGNAL LIST

See Appendix D. in the following Report - R/H-20-13-83/84

E. PNEUMOFATHOMETER CALIBRATIONS

No pneumofathometer calibrations were required for the survey of AWOIS No. 02729 and No. 02730.

F. DIVING REPORTS

Diving operations for AWOIS No. 02729 and No. 02730 were not conducted due to excessive depth.

H. LOCAL NOTICE TO MARINERS REPORT

Negative Report

J. DANGER TO NAVIGATION REPORT

See Appendix H.

HYDROGRAPHIC TITLE SHEET

FE-257 WD

INSTRUCTIONS - The Hydrographic Sheet should be accompanied by this form, filled in as completely as possible, when the sheet is forwarded to the Office.

FIELD NO.

R/H 20-13-83/84

StateNEW YORK	V
General locality LONG ISLAND SOUND Southeast of Sixmile Recf CORRIDOR POINT 7 TO LONGITUDE 072-20-00 W	V
Locality CORRIDOR POINT 7 TO LONGITUDE 072-20-00 W	
Scale 1:20,000 Date of survey 15 SEP	T. 83 - 29 OCT. 84
Instructions dated 22 JULY 1983 & 12 APRIL 1984 Project No. OPR-	B660-RU/HE-83/84
Vessel NOAA SHIPS RUDE (9040) and HECK (9140)	
Chief of party LCDR ROBERT K. NORRIS	~
Surveyed by LCDR R.K. NORRIS, LCDR D.D. WINTER, LT N.G. MILLET LT J.C. TALBOTT, LTJG T.G. CALLAHAN Soundings taken by echo sounder, hand lead, pole RAYTHEON DSF 6000N S/Ns RAYTHEON DE-719B S/Ns	
Graphic record scaled by T.G.C., E.M.C., W.J.A.	and Wire Dr
Graphic record checked by R.K.N., D.D.W., N.G.M., E.M.C., T.G.C., W.J	.A
Protracted by N/A Automated plot by	N/A
Verification by Hydrographic Surveys Branch, Evaluation and Analysis Gr	oup, A.M.C. Smooth Tides
Soundings in the state of the s	CTED TIDES. Applied
REMARKS: All times are recorded in UTC. See FE-257WD, Coast P OPR-B660-RU/HE-83/84, Loran-C Comparison Data for OPR-B660-RU	
Horizontal Control Report for OPR-B660-RU/HE-84 for additional	l information on
this survey.	
*	




TABLE OF CONTENTS

	DROGRAPHIC TITLE SHEET	
PRO	OGRESS SKETCH	11
	BLE OF CONTENTS	
Α.	PROJECT AUTHORITY	1
В.	CHARACTERISTICS AND LIMITS OF SURVEY	1
	SURVEY VESSELS	1
D.	HYDROGRAPHIC SHEETS	ī
υ .	EQUIPMENT AND TECHNIQUES	2
E.	CONTROL STATIONS	3
r.	CONTROL STATIONS	4
	CALIBRATION AND POSITION CONTROL	5
Η.	DATES OF SURVEY	
I.	REDUCTION AND PROCESSING OF DATA	5
J.	JUNCTIONS AND SPLITS	7
	COMPARISON WITH PRIOR SURVEY	7
L.	COMPARISON WITH THE CHARTS	8
М.	ADEQUACY OF SURVEY	9
N.	INCOMPLETE ITEMS	9
	HANGS AND GROUNDINGS	10
	CURRENTS AND WINDS	10
Γ.	PERSONNEL	10
	GENERAL NOTES	10
		11
S.	APPROVAL SHEET	11
	PENDICES	a 1
₩A.	ABSTRACT OF ELECTRONIC CORRECTORS	A- 1
∦B.	ABSTRACT OF DAILY STATISTICS	A-13
	HORIZONTAL CONTROL	A-15
D.	SIGNAL LIST	A-16
Ε.	PNEUMO DEPTH GAUGE REPORT	A-19
F.	DIVING REPORT	A-20
∗G.	SHEET PARAMETERS	A-21
	LOCAL NOTICE TO MARINERS REPORT	A-23
	SMOOTH TIDE REQUEST - FIELD TIDE NOTE	A-24
.7.		A-28
	TRANSMITTAL LETTERS	A-29
γ.V.•	SIDE SCAN SONAR COVERAGE ABSTRACT - TARGET ABSTRACT -	
ъ.		A-39
L 38	TARGET LIST	
κ Μ.	SETTLEMENT AND SQUAT DATA GEOGRAPHIC NAMES LIST (Field)	A-40
₩N.	GEOGRAPHIC NAMES LIST 17.5.94	W-21
Ο.	SOUNDINGS APPLIED TO FIELD SHEET	A-53
SUI	PPLEMENTAL APPENDICES - Additional 1984 field work	
ŁΔ	ABSTRACT OF ELECTRONIC CORRECTORS - BASELINE	
W. 27 •	CALIBRATION DATA	B- 1
V D		B-11
		B-15
	Didining Did to the total tota	
		B-17
⊁ I.		B-19
₩K.	TRANSMITTAL LETTERS	B-22

DESCRIPTIVE REPORT TO ACCOMPANY
HYDROGRAPHIC SURVEY

FE-257WD (FIELD NO. R/H 20-13-83/84)
SCALE 1:20,000
1983/84

NOAA SHIPS RUDE & HECK LCDR ROBERT K. NORRIS, COMDG.

A. Project Authority

This project was conducted during a two year period in accordance with Hydrographic Project Instructions OPR-B660-RU/HE-84 and OPR-B660-RU/HE-83, Southern New England Coast. The 1984 instructions are dated April 12, 1984, with two ammendments to these instructions, change No. 1 dated May 21, 1984 and change No. 2 dated Nov. 30, 1984. The 1984 instructions supersede the previous instructions issued for OPR-B660-RU/HE-83, dated 17 June 1983, with two changes to those instructions, dated 22 July and 8 December, 1983. The purpose of this project is to provide wire drag and side scan sonar clearance of the Northville Industries Corporation oil tanker route, to provide clearance depths over selected wreck sites, and to verify or disprove certain reported submerged wrecks along the south coast of New England.

H-10162 WD

B. Characteristics and Limits of Area Surveyed

This report contains that area of the one mile wide tanker route, which junctions with R/H 20-12-83/84 to the west at corridor point 7, longitude 072-30-00 W, and to the east with survey R/H 20-14-83/84 at longitude 072-20-00 W. The survey work consisted of an initial side scan sonar investigation of the corridor with 100-percent coverage of the bottom, which was conducted in 1983. 1984 operations consisted of a wire drag survey of AWOIS item 2729 and the boulder field contained within the tanker corridor. The drag extends 4.2 lineal nautical miles from southwest at longitude 072-26-28 W to northeast at longitude 072-21-332 W. This wire drag completed the opposing drag requirement for AWOIS item 2729 from FE-257WD (1983). The data has

C. Survey Vessels

The NOAA Ships RUDE (vesno 9040) and HECK (vesno 9140) were the only two vessels used in this survey. Both ships were used for the side scan sonar coverage and the wire drag operations.

D. Hydrographic Sheets

The hydrographic sheets used in this survey were made of mylar and were constructed with the Digital PDP 11/34 computer, serial number AG22645 and Houston Instruments roll-bed plotter, serial number 8731-8 aboard the Ship RUDE.

The field sheets and boat sheets were plotted at a scale 1:20,000 and were used aboard each vessel to hand plot .towing vessel's position while on line. sheet A smooth also plotted aboard the ship using the same equipment This smooth sheet was used to machine plot the described above. towing vessel's position, to hand plot any targets or large contacts, to delineate the limits of rocky or boulder areas, and to illustrate the area covered by side scan sonar operations.

two A & D (area and depth) sheets were hand plotted a scale of 1:20,000 and depict the wire drags for each year. strips 01 and 03 for JD 236 of 1983 were forwarded to Atlantic Marine Center with survey R/H 20-11-83, FE-257WD. drags were hand plotted to provide reference for desired opposing drags of the AWOIS items 2729 and 2730. It was also necessary to hand plot the A & D sheet containing the drag strip 01 of JD The Del Norte ranges from the electronic 1984. stations exceeded the limits allowable for the wire drag programs. The drag data could not be machine plotted using standard R/H Double Precision W/D Programs <

The remaining field records for this survey are being ٥ŕ۶ the Atlantic Marine Center for future reference The computer plotted Lattice on the boatsheet for NEW LONDON LEDGE LIGHTHOUSE, 1932 is in error coursing the strip to plot in a slightly different position than planned by the field. However the corrected strip achieves the intended verification and smooth plotting.

E. Equipment and Techniques

The ship wire drag work was performed using standard wire The drags were tested from the drag equipment and techniques. ships' Sisu launches.

side scan sonar coverage was accomplished with the Klein side scan sonar systems. Two Klein systems were provided by the Atlantic Marine Center. Each system consisted of a Model 521 recorder, a 100 KHz towfish, a K-Wing depressor and a towcable. The Model 521 recorder used aboard the HECK, serial number 223, settings. initial and maximum gain control with numerical This allowed for annotating of the sonargram at the start of the day and annotating any change in the settings that occurred during the day. The recorder aboard the RUDE, serial number 088, did not have numerical settings on the gain control knobs. sonargrams from this recorder were only annotated with the relative changes that were made to the gain settings during day's operations.

The recorder 088 also did not have as many paper take-up rollers as did recorder 223. This caused the sonargram record produced by recorder 088 to contain numerous paper pull stretch These stretch marks appeared as diagonal traces from the 🗸 outer edge of the paper towards the center, as the paper came off helix drum. All the sonargrams from this recorder were annotated as to this fact to avoid confusing these stretch marks with sand waves.

Norte rates obtained on fixes were recorded with Del 7000+ serial printers during this survey. These Model Eaton printers worked fairly well considering the fact that they were not designed to be operated in a marine environment. The printers would often type out a line of meaningless characters or from the previous fix before the current fix was recorded.

printer records were annotated such that these meaningless characters and extraneous rates were lined out leaving the correct fix rates clearly displayed.

In accordance with the 1983 Project Instructions Change No. 2, a method was developed and utilized running nine equally spaced tracklines along the length of the corridor at the 200 meter range scale. This method provided complete and adequate

coverage of the corridor, at 100% coverage.

A Raytheon model DE-719B echo sounder was operated and annotated concurrently during all 1983 side scan sonar and wire drag operations. Unit S/N 5799 was operated aboard the RUDE and unit S/N 6212 was used aboard the HECK during this survey. The echo sounder recordings were reviewed daily to ensure that no large objects located directly under the sonar towfish may have been undetected. A DSF 6000N echo sounder was operated aboard both towing vessels during 1984 wire drag operations. Unit S/N B051N was used aboard the RUDE and the unit S/N All6N was operated on the HECK.

Although it is not anticipated that these sounding records will be used for charting purposes, the settlement and squat data for the RUDE and HECK, obtained in Norfolk Harbor on 25 January 1983, is included in this report. No velocity corrections or settlement and squat determinations were actually conducted within or during this project. The draft of the transducers on both vessels is 7.0 feet.

F. Control Stations

The soundings recorded were apparently not dotted by the field and no automated tapes of these soundings were submitted therefore no plot of these soundings is available. The soundings collected are of reconnaissance value only and not intended for charting.

Three electronic control stations were used for this section of the survey. These stations were:

Station Name	Latitude & Longitude	Elev.
FALKNER ISLAND LIGHTHOUSE (1882)	41-12-42.701" N 072-39-14-608" W	28.6 m/
NEW LONDON LEDGE LIGHTHOUSE (1932)	41°-18′-20.79¥2″N 072°-04′-40.51¥2′W	17.7 m
SAYBROOK LIGHTHOUSE (1861)	41°-16'-16.894",N 072°-20'-37.01X9W	21.6 m/

These stations were located by NGS and the adjusted positions for these stations were obtained from published NGS horizontal control data. All stations are of Third-Order, Class I control accuracy or better. The station positions are based upon the North American Datum of 1927.

The 1983 control for side scan sonar work was accomplished using FALKNER ISLAND LIGHTHOUSE as Sta. 01 and SAYBROOK LIGHTHOUSE as Sta. 02. SAYBROOK LIGHTHOUSE, Sta. 01, and NEW LONDON LEDGE LIGHTHOUSE, Sta. 02, were used in 1983 for control in positioning Cornfield Lighted Bell Buoy "CF" and Cornfield Shoals Dumping Ground Lighted Buoy "A". The 1984 wire drag survey used control at SAYBROOK LIGHTHOUSE, Sta. 01, and Sta. 02 at NEW LONDON LEDGE LIGHTHOUSE.

G. Calibration and Position Control

Vessel positioning for all work was accomplished with the Del Norte 520 series electronic positioning equipment operated at a frequency of 9400 MHz in the range-range mode. A listing of DMU and master units used by the vessels during this survey are listed by Julian day in Appendix A for the 1983 work and in Supplemental Appendix A for the 1984 operations. During 1983, remote unit 74, S/N 3003, was installed at FALKNER ISLAND LIGHTHOUSE and later at NEW LONDON LEDGE LIGHTHOUSE. The remote ~ installed for the 1983 survey at SAYBROOK LIGHTHOUSE was unit 76, The remote units were changed to 80 series coding 1984. The change was necessary due to other users operating Norte 520 equipment with 70 series coding concurrently during the 1984 wire drag survey. Remote unit 84, S/N 3033, was operated at SAYBROOK LIGHTHOUSE and the unit coded 86, S/N 3004, was installed at NEW LONDON LEDGE LIGHTHOUSE.

A total of five baseline calibrations were performed during this survey. All baseline calibrations were conducted in the immediate work area and entirely over water in accordance with AMC OPORDER 79. Baseline calibration distances were determined by the HP 3800A electronic distance measuring instrument, serial number 0987A00157. The following is a list of the baseline calibrations, as measured by the HP 3800A:

27 August, 1983	Belle Terre Beach to Port Jefferson W. Jetty Lt.	2601.1 m
30 October, 1983	New London NUSC Pier 4S to S. Groton Jetty	2312.0 m
15 November, 1983	New London NUSC Pier 4S to S. Groton Jetty.	2312.0 m
28 September, 1984	Newport Naval Pier 2 to Gould Island SE Pier	1933.2 m
29 October, 1984	New London NUSC Pier 4S to S. Groton Jetty	2312.0 m

Daily calibrations in 1983 were accomplished using the fixed point calibration method in accordance with Hydrographic Manual section 4.4.3.3. KELSEY POINT BREAKWATER LIGHT(1934) was the fixed point used during this survey. All ship calibration was accomplished by carrying out the calibration to the ship via a launch equipped with Del Norte.

The launch pulled as close alongside the breakwater light as possible. The Del Norte equipment was then calibrated, the offset applied, and the correctors determined. This calibrated launch then pulled alongside the ship, as close to the ship's Del Norte antenna as was safely possible. Rates were then compared, offsets applied, and a second set of correctors generated. These two sets of correctors, between the launch and the light and between the launch and the ship, were then added together and the ship's calibration correctors determined.

Not an acceptable method of calibration, see the Evaluation Report.

The HECK open calibrated in this manner on JD 258 of 1983. The calibration correctors obtained between the launch and the light and between the launch and the ship were combined and entered in Sounding Volume 1. There was no closing calibration on this day due to darkness.

The calibration data from JD's 277 and 278 of 1983 is contained in Appendix A, of this report. The RUDE open and close calibrated on JD 277 with no difficulties. On JD 278 the RUDE and HECK open calibrated but were unable to close calibrate due to high winds and seas. These conditions prevented putting a launch

over the side without endangering personnel.

The calibration data for 1984 consists only of JD 299. The opening and closing calibrations were conducted using three point sextant fix procedures in the vicinity of Sarah Ledge, west of the entrance to the New London Harbor Channel of the Thames River.

The daily correctors for all calibrations were stable and within accuracy tolerances for a survey of this scale. Therefore, only baseline calibration data should be applied to the raw position data during final processing and smooth plotting. Concur

H. Dates of Survey

This survey period for 1983 was begun on 15 September, (JD 258) and was completed on 3 November, (JD 307). The only operation conducted in 1984 for this survey was the wire drag on 25 October, (JD 299).

I. Reduction and Processing of Data

Data collected during ship drag operations for 1984 was manually entered in the wire drag volumes while on line. The position data was also entered in the Digital PDP 11/34 computer while on line. The programs used were the R/H Double Precision Wire Drag programs. However, these programs were unable to machine plot the drag strip data. Review of the Del Norte ranges from the electronic control station indicated that the rates exceeded the limits for this program. The positions were then hand plotted on the A & D sheet for JD 299. The effective depths from the reduced data were then drawn on the drag strip in colored pencil.

Test data was applied to the drag in a manner which differs slightly from the Wire-Drag Manual. This method has been used aboard the drag boats for the past several years and is a more conservative method. If the amount of lift increased during a drag when uprights remained unchanged, this decreased drag depth was applied back to a time halfway between the time of the earlier test with less lift and time of the later test with the greater lift. Lifts were recompeted during verification and were applied in accordance with the greater lift. Drag Manual.

Predicted tide correctors were then applied to the drag

Predicted tide correctors were then applied to the drag depths obtained. The predicted tide data applied to the 1984 wire drag section of this survey was obtained from correctors based on latitude 41-10-00" N and longitude 072-28-00" W. These are correctors for the AWOIS item originally numbered # 1814, which

This is not in accordance with accepted practices. During verification changes were applied in accordance with the Wire Drug Manual.

was renumbered (July 20, 1983) AWOIS No. 2729. The predicted tide correctors were generated onboard the RUDE with the ships' Digital PDP 11/34 computer and predicted tide tapes for 1984. These tide tapes were supplied to the ships by MOA 231. Hardcopy printouts of the predicted tide correctors used during the 1984 wire drag survey operations are included in the data files.

The changes in effective depth that occurred during the drag were applied at the exact time of the change. The fix interval for the drag work was five minutes, therefore some changes in effective depth occurred between fixes. When this occurred the time was interpolated and drawn in appropriately.

All side scan sonar data was initially recorded in NOAA Form 77-44, Sounding Volumes. All header data, position numbers, time, and position control data were recorded in the appropriate columns in the volumes. The remarks column was used to record all line information, vessel rpms, length of towcable, vessel heading, and any other unusual or noteworthy remarks.

Vessel position data from the side scan sonar work was entered in the Digital PDP 11/34 computer with a modified version of the R/H Double Precision Wire-Drag program. Rates for just one vessel were entered in this program and a single vessel position plot was generated with the Houston Instruments roll-bed plotter. All side scan sonar work for this survey was plotted in this manner.

Side scan sonar coverage was computed and listed on the Side Scan Sonar Coverage Abstract. The required 100% side scan sonar coverage was obtained throughout the corridor, with the exception of the area between fixes 1110-1113 and 1538-1535 (smooth sheet numbers 110-113 and 538-535). This area was swept in 1983 by wire drag on JD 236, strip 01, to a depth of 76 and 75 feet. An additional wire drag was conducted in 1984 on JD 299, and strip 01 cleared the same area in the opposing direction. This clearance depth was computed using predicted tides and is fully documented in the Descriptive Report accompanying contemporary survey R/H 20-11-83 (FE-257WD).

The sonargrams from the side scan sonar work were examined while on line and then again at the end of the day. All These notable contacts were flagged during each examination. flagged contacts were then logged in the Side Scan Sonar The Target Abstract was then Abstract for that field sheet. completed and the contacts were plotted on the smooth sheet containing the vessel position plots. The Side Scan Sonar Target Lists were then compiled from the Target Abstracts and the The Del Norte rates of the contact positions were contact plots. determined using a grid and arc overlay. These rates were then used to determine the latitude and longitude of the contact with the HP 9815 computer and the Geodetic Package program.

The towfish length indicated in the sounding volume and on all sonargrams is actually the length of towcable from the waterline to towfish. During the plotting of the contacts on the smooth sheet, the towfish layback was computed by adding the length of towcable from the waterline to the towfish plus the antenna to waterline distance (17.98m).

The computation of the towfish layback is not an exact determination of the layback but is an adequate method of plotting contacts. It is realized that there are two minor errors in using the length of towcable out the stern as a measurement. First the towfish is not directly astern of the towing vessel. Secondly, the actual horizontal component is less than the entire length of towcable deployed due to the depressing effect of the K-Wing on the towfish. This amount of error is insignificant when plotted at a scale of 1:20,000. There was good agreement between the plots of the same contact as observed on adjacent lines run in opposite directions.

J. Junctions and Splits - Also see section 5. of the Evaluation Report.

-H-10162 WD

This side scan sonar survey junctions with contemporary survey R/H 20-12-83/84 to the west and with contemporary survey $FE-26840 \rightarrow R/H$ 20-14-83/84 to the east. There is adequate overlap with these

contemporary surveys - Concur

Contemporary survey R/H 20-11-83 (FE-257WD) which investigates AWOIS items 2729 and 2730, was contained in the work area. Both of these drags were hand plotted on the A & D sheet for 1983. AWOIS item 2729 was cleared in 1983 by a wire drag to 75 feet and in one direction, from northeast to southwest. This drag strip, JD 236-01, effectively clears the area not covered by 100% side scan sonar search. The 1984 wire drag operations are depicted by the hand plot of drag strip JD 299-01. This drag was conducted from southwest to northeast and clears the 1983 drag of AWOIS item 2729 in the opposing direction with an effective depth of 73 feet.—R/H-20-11-83 was combined with R/H-20-13-83/84 into FE-257 WD.

K. Comparison with Prior Surveys - Also see Sections 62 & 66 of the Evaluation Report.

The side scan sonar and wire drag records were compared with prior surveys H-9089 (1969) and H-9181 (1970-71). The boulder field centered around $41-10-00^\circ$ N, $072-23-00^\circ$ W was identified as a prominent feature which was not indicated on the prior survey.

The section of the boulder field noted as target number 12 on the Target List appears to be a field of small rocks and, according to prior survey H-9181 (1970-71), occurs in over 100

feet of water.

Selected soundings obtained on the peaks of sand waves during side scan sonar operations with the Raytheon DE-719B fathometer are listed in Appendix O. These soundings are corrected for draft, settlement and squat, and predicted tides. The predicted tide correctors used are those for AWOIS item 2729 at latitude 41-00-00" N, longitude 072-28-00" W. These soundings are applied to the smooth sheet and compared with the prior survey H-9181. In the areas of sand waves, soundings obtained by this survey are 2-10 feet shoaler than those on the prior survey.

These shoaler soundings may be due, in part, to differences between actual and predicted tide correctors. There is also the possibility that some shoaling has occurred in the area of sand waves since sand wave bottom topography is very dynamic in nature and changes with each storm cycle. Concur

These soundings are not plotted on the final field sheet.

L. Comparison With the Chart-See the Evaluation Report, section 7.a.

The chart that covers the work area is NOS chart 12354, 26th Ed., Feb. 4/84. When comparing soundings found on the above chart with prior surveys H-9089 and H-9181, two soundings were charted which did not agree with the prior survey. These two charted soundings were:

Prior Survey	Latitude	Longitude	Survey Depth	Charted Depth
H-9181	41°-08′-09′N	072–28–30″w	110 feet	97 feet
H-9181	41°-08′-48′N	072–28–24w	113 feet	102 feet

These two soundings are beyond the survey limits of H-9181 and originate with prior survey H-1591 (1883).

It is recommended that the prior survey be researched to find out the origin of these charted soundings.

Regarding non-sounding features, the following charting recommendations are offered:

Chart "Blds," at : 1. 41-10-04"N, 072-23-07" > Concur

 $41^{\circ}-09^{\circ}-48^{\circ}N$, $072^{\circ}-22^{\circ}-45^{\circ}N$ Chart "rky" at: 2.

rt "rky" at:
41-11-10.1", 072-18-51.8" and for the notation large migrating sand waves 3. Chart a sand wave symbol, "nat :

41-08-48N, 072-27-54W 41-08-42N, 072-26-48W

41-09-35N, 072-26-15W

41-09-48N, 072-24-45W

41-10-50N, 072-20-20W 41-11-36N, 072-19-18W

41-11-20N, 072-18-48W.

All floating aids to navigation were checked during the course of this survey. Cornfield Lighted Bell Buoy "CF" is contained in and plotted on the smooth sheet. This plotted position agrees with the buoy position given in the Light List and with the charted position on NOS chart 12354, 26th Ed., Feb.

Cornfield Shoals Dumping Ground Lighted Buoy "A" is not contained on this sheet but was positioned during and with control from this survey. The position obtained by this survey for this buoy is $\lambda41^{\circ}-12^{\circ}-33.0$ N, ϕ 072°-21-16.5 W. This plots the buoy \checkmark 0.2NM east of the position that appears in the Light List and the position from NOS chart 12354, 26th Ed., Feb. 4/84. This private aid was changed during the 1984 season to CORNFIELD SHOALS DUMPING GROUND LIGHTED BUOY "DG1" for confirmation and additional information on this aid.

Sixmile Reef Lighted Whistle Buoy "8C" and Twenty-Eight

Foot Shoal Lighted Bell Buoy "TE" are contained within the limits of this smooth sheet but were positioned during contemporary dashsurvey R/H 20-12-83/84. The positions of these buoys were checked and confirmed during survey R/H 20-12-83/84 and are not plotted on sheet $R/H_{20}-13-83/84$.

All Λ landmarks in the proximity of this survey were visually verified from offshore and are adequate for charting.

M. Adequacy of Survey

With the exception of the area mentioned in section I., 100% side scan sonar coverage was achieved in the section of the tanker corridor contained within the limits of this sheet. This area, lacking 100% sonar coverage, was cleared during wire drag operations in 1983 and 1984 and is addressed in section I. The 1984 wire drag work also completely cleared the boulder field centered about latitude 41-10-00"N and longitude 072-23-00"W with a minimum effective depth of 7% feet. Therefore, this survey adequately covers the tanker corridor, contained within the limits of this sheet, by side scan sonar and wire drag operations. See section N. of this report for additional survey operation recommendations.

Time constraints during the 1983 field season precluded the investigation of any side scan sonar contacts in the tanker corridor which were not cleared by the wire drag operations for AWOIS item 2729. The boulder field, centered around $41^{\circ}-10^{\circ}-00^{\circ}N$, $072^{\circ}-23^{\circ}-00^{\circ}N$ contained many significant contacts within the tanker corridor. This area was cleared by a wire drag strip 01 on JD 299 of 1984 to insure that no hazards to navigation exist within this boulder field.

Review of the 1983 Target List indicated the contacts labeled lla, 37, 38b had computed heights of nearly 10 feet and occur in 114 feet of water. These targets could possibly constitute a hazard to deep draft traffic and require additional wire drag investigation, which was conducted in 1984. The targets lying adjacent to the boulder field mentioned above were also cleared by wire drag survey on JD 299 of 1984. This drag cleared all of these recommended contacts and the majority of the corridor between longitudes 072-21-352W to 072-26-304W with a minimum effective depth of 73 feet in one direction from southwest to northeast. These contacts have computed depths of over 100 feet and do not constitute. The Target labeled 12, a boulder field, does not contain

The Target labeled 12, a boulder field, does not contain any significant contacts and occurs in over 100 feet of water. Therefore, it does not constitute a hazard to deep draft vessels. It is not recommended that Target 12 require clearance by wire drag survey or any further investigation. This target was cleared by wire drag survey or any further investigation. Junctional survey FE-268 WD

With the exception of the targets mentioned above, the

With the exception of the targets mentioned above, the Side Scan Sonar Target List does not indicate that any other contacts observed during this survey exceed a height greater than 10% of the charted depth. Any further investigation of these targets, other than those mentioned above, is not recommended at this time. Concur

AWOIS item 2729 was cleared to 75 feet in 1983 and to a minimum effective depth of 73 feet in 1984 in the opposite direction by the drag on JD 299.

. N. Incomplete Items

The Command feels that sufficient development of the survey area was achieved by side scan sonar, wire drag or by the combination of these operations. The survey has satisfied the intent of the project instructions and, in this respect, has no incomplete items.— Concur

O. Hangs and Groundings

No hangs were encountered during the wire drag operations.

P. Currents and Winds

Tidal currents were closely monitored during the course of this survey. Ship drag operations had to be run with the predominate current flow to result in satisfactory lift data. Side scan sonar operations were also conducted with the predominate current flow to maintain proper towfish depth. Comparisons were made with the Tidal Current Tables, 1983/84, Atlantic Coast of North America for station 2731. In general, the times and strengths of maximum flood and ebb or times of slack water at the surface agreed with the predicted times and strengths under normal conditions.

In general, the surface and bottom tidal currents appeared to exhibit the same general characteristics and trends as the nearshore areas. A complete description of these conditions are available in the Descriptive Report for survey R/H 05-01-83/84, R/H 05-03-83/84, and R/H 10-02-83.

Q. Personnel

The officers participating in this survey were LCDR Robert K.Norris, LCDR Donald D. Winter, LT Neal G. Millett, LT Edward M. Clark, LT Joseph C. Talbott, and LTJG Thomas G. Callahan.

R. General Notes

See the Coast Pilot Report and Loran-C comparisons for OPR-B660-RU/HE-83, Descriptive Report for AWOIS Item 2729 (R/H 20-11-83), Horizontal Control Report for OPR-B660-RU/HE-84, and the Descriptive Report for OPR-B660-RU/HE-82 for additional information on this survey.

The format of this report is a composite of the Descriptive Report formats contained in the Wire Drag and Hydrographic Manuals. This format is the optimum composite of the pertinent sections of the two reports and is more applicable to the surveys currently being conducted by the Rude and Heck.

Charting recommendations for this survey are contained in section L. of this report.

Survey R/H 20-11-83 (FE-257WD) should be reviewed with the additional wire drag data clearing AWOIS item 2729 from this survey. R/H-20-11-83 $\frac{1}{5}R/H$ -20-13-83/84 have been combined into one survey — FE-257WD

Respectfully submitted,

Edward M. Clark Jr, LT. NOAA

S. Approval Sheet

Field operations contributing to the accomplishment of this survey were conducted under my supervision with frequent personal checks of progress and adequacy. The report and the associated field sheets have been closely reviewed and the completed work is considered adequate.

Robert K, Norris, LCDR, NOAA

Commanding Officer

NOAA Ships RUDE and HECK

C. HORIZONTAL CONTROL

No new stations were established for this survey. See Appendix D, Signal List, for a complete listing of all stations used on this survey.

D. SIGNAL LIST

Appalado

OPR-B660-Ru/He-83 - R/H-ZO-11-83

See the Automated Control File Listing following these lists.

	Control The Listing
Saybrook Lthre (1861)#2	
ID NBR 15	
LAT 4116,16.894"~	$\sim \Delta_{\rm col}$
LON 722037.01 %9 "	Seaside Sanitarium
ELEV'N 21.60 M	Etay. Tank
711F	
FILE 15	ID NB R 1 LAT 41813.03
	LON 728757.66
Libby's Chimney (1934)	FILE
ID NBR 16	rile i
LAT 41,15,23. 512 ,20"	
LDḤ 722832.760″∕	Bartlett Reaf Lt.
FILE 16	ID HBR 2
	LAT 4/16%7.92
New London Harbor	LON 720813 74
thse.	
ID NBR 17	FILE 2
LAT 4X859.489	
LON /20324.855	Seaflower Reef Lt.
ELEW N 27 10 M	
FILE 17	ID NBR 2
FILE i7	LAT 41 45.24
	LON 720281.46
New London Ledge thise.	20200.40
thse.	FILE 2
ID HBN 18	
LAT 4 1820.795	
LON 720 40.516	
ELEV'N 1 70 M	

	Apple D - R/H-20-1	//-83 /:+-
PROJECT: B660-Rulle-83	Faking following these ID NBR (1882)	Southwest Ledge Lt. ID NBR 10
SIGNALS/STATIONS	LAT 411242.701 LON 723914.608 LON 723914.608 MV	LAT 4 1403.681 LON 725445.178
Horton Point Lt.	FILE 5	FYLE 10
ID NBR 1 LAT 19597.828 LON 722645.981 ELEV'N 31.00 M	New Haven West Brkw. West End Links	Saybrook Brkw Lithse. ID NBR 11
FILE 1	ID NBR 6 LAT 41 331.939 LON 725 23.754	LAT 4:1547.185 LON 722835.611 ELZV'N 17.70 M
Tank 8	F&LE 6	FILE 11
ID HER 2 LAT 105847.362	New Haven Lt.	Duck Is. North Brkw Lt. (1934)
LON 723849,172 ELEV N 55 00 M FILE 2	ID NBR 7 LAT 11115.430 LON 725633.422	1D NBR 12 LAT 411536.441 LON 722831.536 ✓
Northville Oil	FILE 7	FILE 12
Terminal E. Dolphin	New Haven Middle Brkw East End Lt.	Ouck Is. West Brkw Lt. (1834)
ID MBR 3 LAT 419002.098 LON 723044.971	ID NBR 8 LAT 411852.659 LON 725524.882	ID NBR 13 LAT 411522.266" LON 722908.296"
F ILE 3	FILE 8	FILE 13
New Haven Lthse.	Now Haven Middle Brown. West End Lt.	Kelsey Paint Brkw LT.
LAT 4/1455.931 LON 725415.238 ELEY N 36.60 M	ID NBR 9 LAT 1327.229 LON 725611.308	ID NBR 14 LAT 411436.323 LON 723030.849
FILE 4	FILE 9	FILE 14

PROJECT:	fakner Is Lthse (1882)	Southwest Ledge Lt.
B660-Ru/He-83	ID NBR . 5	
R/H 20-13-83 /	LAT 41°12'42.701"	ID NBR 10 LAT 411403.681
"SIGNALS/STATIONS	LON 723914.608 ELEV'N 28.60 M	LON 725445.178
Horton Point Lt.	FILE 5	FILE
ID NBR 1 LAT 412597.928	Hew Haven West BAW.	Saybrook Brkw Ltpse.
LON 722645.981	West End Light	
ELEV/M 31 00 M	ID NBR 6	ID NBR 11 LAT N112747.185
	LAT . 411331.939	LON 722035.611
FILE	LON 725723.754	ELEV'M 17 70 M
Vank 8	FILE	FILE
ID MBR 2	New Haven L.T.	Ruck Is.
LAT 492847.362	12 ::55	North Brkw Lt.
LON 7 23849.172 ELEV N 55.00 M	ID NBR 7 LAT 411815.430	ID_NBR 12
	LON 725638,422	LAT 47.536.441
FILE	/	LON 722831.536
	VILE >	FILE N
Northville Oil	M II M III P &	
Terminal E. Dolphin	New Haven Middle BAKW East End Lt.	Ouck Is.
ID NBR 3		West Brkw Lt.
LAT 420002.098	ID NBR 8	ID NBR 13
LON 723844.971	LAT 411352.659 LON 725584.882	LAT 11522.266
ELE		LON 722908,296
•	F.LE 8	FILE N
Hew Haven Lthse.	Hew Haven Middle Botow.	
Old Tower	West End Lt.	. Kelsex Point Brkw Lt. /
ID NBA 4	ID NBR 9	ID NBR 14
LAT 411455.931 LON 725115.238	LAT\ 4.1327.229	LAT 411436.323"
ELEV'N 26 60 M =	LON 725611.308	LON 723030.849"
	FILE 9	FILE 14
FILE 📉	No. 1	1 1 1 1

OPR-B660-Rulle-83 - R/H-20-13-83

See the Automated Control File Listing following these Lists.

. Saybrook	thre. [1861]
ID HER	15
LAT 411 LON 722	616.894 / 037.01 X 9
	21.60 MV
FILE	<u>i</u> 5
Libby's C	himnes
ID NEC	16
LAT 4	523.512

•	New!	London	Har	bor
•		thse.	(18	35)

ID NBR LAT LON ELEV'N	41 1 13	524.	
ETIE	•		i 7

ID MBR	_	18
	411820.	
LÖN ?	72ัย44ย.	
ELEV'N	177.7	0 M⁄

_	-	-	_	-	-	-	_	_	_	_	_	-	_	_	-
-	Ĭ		-												E

Seaside Sanitari	ium
Elev. Tank	(1232)
th NOO	19

ID NBR		19
LAT	41'18'13.	
LON	728757.	667 "/

FILE is

. Bartlett Reaf Lt. (1954)

ID NBF LAT LON	(41 [°] 16⁄27, 72°0815.	20 ,924″/ ,740″/
CTIC		20

Seaflower Reef Lt. (1954)

ID MBR	21
LAT	41°17′45.245″/
LON	72°02′01.462″/
FILE	

OPR-8660-RUME-84

SIGNALS/STATIONS

TOWER (1972)

- 		
ID NBR	. /	1
LAT 41	1/520.64	?
LON	0 035.15	
ELEY A	44.88	m
7111	`	1

BARTLETT REEF LT.

111	HBR					3
LAT		4i	16	27	.92	4/
		72	98	15	.74	₫√
FIL	Ξ				•	3

J NEW LONDON HARBOR LIGHTHOUSE (1835)

T T.	198				4
LOT	. :	411	959	48	9/
104		728	524	.85	5/
				' <u>-</u>	-
FIL	<u> </u>			•	4

LIGHTHOUSE (1932)

ID MBR	5, 5
LAT 41	1828.79 %2 ″
LON 72%	3440.51 %2 "
ELEVIN	17.70 MV

<u>L.</u>	•	:	Ξ		•			5

SEAFLOWER REEF LT.

ID MB	**		5
LAT	4117	15.	245"
LON	72021	31.	4521/

_	7	L	Ξ	 - 1	 	2
Ţ	į	Ļ		e.,	•	

NORTH DUMPLING

ID ME	3 R		7
I OT	,, ,0	715	≎? X 4′
LBT	7 1		984°
LON	728	diii.	9842

-		_	-	-	 	 _	_	_	_	_	_	
14.	-	1	E									?

(1886)

(168e)	
ID HBR	8
LRT 4)	X 015.871
LON /71	568(684
Z -	. X

RACE RU	CK LIHS	<u>s.</u>
X188	(يد	
ID HER		9
1.67	4)(435	.153
LUN	15052	+1+:
FILE		Ş

TITIE		1814	• /
ID NB			10
LAT	X	(222. 32.	673 476
LUN	/ (2) 		دره. دره
FIF			10

EUSHERS	IS. CG
EUPOL	A (1934)
ID NBA	11
LAT 4	658.787
LON	15641.848
FILE	

SAYBROOM	CTHSE.
ID NAT	12] / 16.894
LON 72 ELEV/N	21 50 H

	N
5aybrook	LTUSE
VAD GLEC	CONTROL
DVENTENTZY	LINED OUT.
	tou evec

FES	<u>!</u> 57		0	5-15-8	5								
#ECO)RD '	YR	STA	CARTO	LABEL V	FCTOR	PLOT	NAME	STATION FRE	-	LÄTTTUDE	INSTITUTE	
NUMB	BER		NUM	CODE	ANGLE	DISP.	CODE		HFIGHT (KHZ)			
,	1 4	83	1	250	340.30	0.52	3	FALKMER ISLAND LIGHTHOUSE, 1882	28_6_149	8 35 _00	41 12 42 701	72 49 14 608	
' a		83	5	250	340.30	0.52	3	SAYBROOK LIGHTHOUSE, 1861	21_6 149	835.00	41 16 16 894	72 20 37:019	
c 3	3	83	3	250	340.30	0.52	3	NEW LUMDON LENGE LIGHTHOUSE, 1932	17.7 149	835.00	41 18 20.792	72 4 40.512	
12 4	<u>a</u>	83	4	139	340.30	0.52	3	KELSEY POINT BREAKWATER	0_0	<u> </u>	41 14 35 323	72 30 30 8/19	
3		83	4	139	328.84			LIGHT, 1934	0_0	0.00	41 14 36.323	7> 30 30 849	
	 6	83	5	139	340.30	0.52	3	NEW LONDOM HARBOR	27.1	0.00	41 18 59_489	72 5 24,855	
18 7	-	83_	5	139	328.84	1.27	3	LIGHTHOUSE, 1835	27-1	0.00	41 18 59 489	72 05 20 855	
)° 20	8	83	6	139	340.30	0.52	3	SEASIDE SANITARIUM	0.0	0100	41 18 13.034	72 7 57.667	
22 (9	83	6	139	328.84	1.27	3	ELEVATED TANK, 1932	0.0	0.00	41 18 13.034	72 07 57_667	
23 24 1 (83	7	139	340.30	0.52	3	BARTLETT REFF LIGHT, 1954	0-0-	0.00	41 16 27 924	72 9 15 740	
25 24 1	1	83	8	139	328.84	1.27	3	SEAFLOHER REEF LIGHT, 1954	0.0	0.00	41 17 45.245	72 2 1.442	
1 1 7	2	83	9	139	340.30	0.52	3	NORTH DUMPLING LIGHTHOUSE, 1874	0.0	0.00	41 17 15.03/	72 1 11_084	
20 30 1	3	83	10	139	328.84	1.27	3	LIBBY'S CHIMNEY, 1934	0.0	0.00	41 15 23.120	72 29 32,760	
32 1		83	11	139	340.30	0.52	3	DUCK ISLAND NORTH	0.0	0.00	41 15 36.441	72 28 31.536	
22 1 1	5	83	11	139	328.84	1.27	۲	BREAKWATER LIGHT, 1934	0_0	0.00	41 15 36.441	72 28 31.536	
35 36 1		83	12	139	340.36			DUCK ISLAND MEST	0.0	0.00	41 15 22,266	72 29 8 206	w with the st
37 38 1		83	12		328.84			BREAKWATER LIGHT, 1934	0_0	0.00	41 15 22.266	72 29 08.296	
40		•			500 D: 0	TILUC	- ·	OATF:					
#IL	E CER	RT IF	IED C	OKRECT		11116	715	DAIF:					

E. PNEUMO DEPTH GAGE CALIBRATIONS NEGATIVE REPORT

F. DIVING REPORTS

NEGATIVE REPORT

H. LOCAL NOTICE TO MARINERS REPORT

NEGATIVE REPORT

J. DANGERS TO NAVIGATION REPORT

NEGATIVE REPORT

L. SONAR COVERAGE ABSTRACT - TARGET ABSTRACT

		Sonar	Coveras	e Abstra	c+ (TOR -B660-1	Pu/He-83	Ithon No.	RJH 20-1 33
Gearch Track Number	Pange Scale	Minimum Townsh Height (m)	Minimum Effective Sconning Rouge (m)	Search Trock Huniter	Range Scole (m)	Minimum Tout h Height (m)	Minimum Effective Scanning Trage (m)	Maximum Track Specifum	Constray. Analysis
//48-//78	200 m	2/m	200 m	1220-1179	200 m	19 m	188 m	270 m	100%
	200	19	188	1269-1221	200	18	178	300	100
1269-1224	200	18	178	1270-1296	200	15	148	325	100
	200	30	200	1296-1298	200	22	200	350	100
1270-1298	200	15	148	1087-1147	400	-	200 approx	280	100
A-40									
1087-1110	400	. —	200 appress	1560-1538	200	21	200	340	100
///0- ///3	400	_	200 approx	1538-1535	200	27	200	410	< 100 See W.D.
1113-1147	400	-	200 abbes	1535-1500	200	22	200	360	100
						<u> </u>			
1560-1500	200	21	200	1561-1589	200	19	188	300	100
<u> 561-1589</u>	200	19	188	1299-1342	200	20	198	350	100
1299-1342	200	20	198	1626-1590	200	20	198	340	100
	·								

SIDE SCAN TAKGET ABSTRACT

DATE 329 15, OCT 4, 5

J.D.<u>258,277,</u> 278

OPR-<u>B660-Ruftle-83</u> RJH 20-13-83

SHIP RUDE / HECK

			_		,	LEAST						· · · · · · · · · · · · · · · · · · ·	DANCE	WIDTH	TOWFISH
TARGET NUMBER	J.D. TIME	FIX	COMPUTED RATES	TOW SPEED	LENGTH OF TOW (M)	DEPTH (FT)	CHARTED DEPTH (FT)	HEIGHT OF FISH R1 (M)	R2 (M)	R3 (M)	R4 (M)	HEIGHT OF TARGET (M/ FT)	RANGE OF TARGET (M)		LAYBACK (M)
10	UCT UCT	112-3	F. 23075'	4Kts	15.2	123.9	132				52	2.46	32.6/	5.22	36.5
2		737-		4	15,2		117	26.5	Posi	tion	Ast	only	:		36.5
3	258	W3-	1, 28435	4	15.2		130	37.5	Pos	tion	Plot	only			36.5
4 3		1217- 1218	R, 16075 E, 18900	4	15,2	_	96		160.5	1			159.25	4.53	36.5
5		1238-	1, 22780 R2 1/6#0	4	25.9		132	34.5	68.0	81,0	*		59.75	14.46	47.2
6		1265-	R, 18900	4	21.3	-	96	18.0	60.0	69.0	*		57.84	9.29	42.6
7a	278	1287-	R, 22850 R, 11865	4	25.9	123.7	132	26.8	37.0	380	42.0	2.52	28.18	1.30	47.2
1	178	1297-	1, 28435	4	25.9		130	33.0	Pos	tion	plot	only			47.2
90	278	/325-	R, 23475	4	25.9	114.7	125	25.0	30.0	31.5	36.0	3.13	20.53	2.14	47.2
10	278	/316- /317	R, 23750 R, 12175	4	25,9	_	141	27.0	450	48.0	*		38.14	3.50	47.2
119	278	1327-	R, 12075	4	25.9	113.0	114	28.0	131.5	/33.0	134.5	0.31	128.55	1.53	47.2
1/2	278	1342			25.9		104		fos 1	An F	of or	ly - Boulder	Fold		47.2
/3	278	15/1-	R, 26740	4	27.4	115.5	117	24.0	120	57.0	52.0	0.46	34.78	10.46	48.7
14	278	1575	1, 26015 R, 10310	4	27.4	106.6	122	25.0	65.0	110.	118.0	1.69	102.38	5.12	48.7
150	278	1524-	R, 23375 R, 12025	4	27.4	129.1	152	32.0	1050	107.0	110.0	0.87	100.28	2.09	487

* No shadow observed on sonargram. No height of target computation.

OPR- B660-Rulle-83

SHIP

J.D. 278

DATE

	- :					LEAST						HEIGHT	RANGE.	WIDTH	TOWFISH
TARGET NUMBER	J.D. TIME	FIX	COMPUTED	TOW SPEED	LENGTH OF TOW (M)	REDUCED DEPTH (FT)	CHARTED DEPTH (FT)	HEIGHT OF FISH R1 (M)	R2 (M)	R3 (M)	R4 (M)	OF TARGET (M/FT)	OF TARGET (M)	i i	
15B)	UCT 278	1524-	RATES E, 23 26 0 E, 1/935	4	27.4	126.6	132	30.0	<i>50.5</i>				41.78	1.80	48.7
150	278	1524-	R, 23290 R, 12040	4	27.4	126.6	132	27.0	37.0	38.5	41.0	1.65	26.95	2.03	48.7
160	278	1525-	L. 23140 L. 12200	4	27.4	120.2	125	25.0	46.5	48.0	51.0	1.47	40.11	1.73	48.7
17@	278	1526-	L 23000	4	27.4	120.5	125	30.0	62.0	63.0	66.0	1.36	54.99	1.13	4817
18	278	1535- 1536	R, 20825 R, 14335	4	27.4	116,3	126	28.5	680	69.5	77.6	2.97	63.03	1.62	48.7
19	278	1544-	1. 18720 12 16400	4	27.4		113	25.5	75.0	+	10.00		71.54	15.60	48.7
J 0	278	1546-	R, 18350 Rz 16835	4	27.4		111.3	24.0	90.0	992	*		87.51	9,23	48.7
21	278	1222	R. 19610	4	21.3	107	108	20.0	/23.0	/240	1260	0.32	121.41	. 1.01	42.6
12	278	1535-	R, 1649 0 R, 19375	4	2%3		196	20.0	115,0	116.1	*		113.30	1.01	42.6
23	278	1570-	R, 19770 R2 15450	4	2/.3		119			2.00	3.5	Sand Wave			42.8
24	278	1573		4	2/.3	117.8	126	24.0	70.5	76.0	82.5	1.89	66.94	5.77	42.6
250	278	1571-	2, 23285 K, 12200	4	21.3	119.2	125	24.0	1	760	र विश	A COLAGO	72.15		42.6
266		1578-	1, 12030	4	21.3	140.9	141	17.5		125			/22.8	1.01	42.6
27	278	1283	R. 26800	4	2/.3	105.7	117	Position	Plot	1	i ik	e - See App	pendix U.		42.6
28	278	1584-	12/0/25	4	21.3	109.7	117	<u></u>	<u> </u>	1_	•	1000 14	" "		12.6
29		1585	27610		21.3	102.7	117	•							42.6

* No Shadon observed on sonorgram. No height computation,

SIDE SCAN TARGET ABSTRACT

DATE

J.D. 278

OPR- 8660-Ru/He-83 RIH 20-13-83

ITEM #

SHIP

						LEAST				-	-				
ARGET	J.D. TIME UCT	FIX	COMPUTED	TOW SPEED	OF TOW (M)	DEPTH (FT)	CHARTED DEPTH (FT)	OF FISH R1 (M)	(M)	R3 (M)	R4 (M)	HEIGHT OF TARGET (M/ET)	(M)	WIDTH OF TARGET (M/FT)	TOWFISH LAYBACK (M)
30	278	1586-	R, 28025 Rx 9770	4 kts	27.4	111.2	104	Position .	Ploto	FSF	ike -	See Apper	odix O.		48.7
31	278	1588-	E, 29360	4	27.4	112.7	130	" "	. "		"	10001	"		48.7
32	278	1590	R. 29470 L 9995	4	27.4	-	90	20.0	64.5	65.5	69.0	1.01	61.64	1.05	48.7
33	278	1596-	K, 27375	4	27.4	96.7	85	Position'	Poto	FS	ike	-See App	aendix O.		48.7
34	278	1601-	2, 25/65 R 11600	4	27.4	110.7	114	28.5	94.5	85.5	99.0	1.01	90.41	1.04	48.7
35	278	1602-	R, 24950	4	27.4		114	28.5	126.0	127.0	*	—	122.96	1.02	48.7
36	278	1603	R. 11685	4	27.4	109.9	114.	28.0	53.0	54.0	58.5	1.24	45,75	1.15	48.7
37	278	1604	R. 12090	4	27.4	102.4		28.0	39.0	41.5	47.5	3.54	30.37	3.15	48.7
38 b	278	1604-	R, 24095 R2 12190	4	27.4	104.8	114	28.0	57.5	58.5	65.0	2.80	51.68	1.11	48.7
39 a	278	1605-	R, 23855 Rz 12400	4	224	101.9	114	24.0	55.0	57.0	62.0	1.94	50.38	2.18	48.7
40	278	1605-	L, 23885 R2 12600	4	27.4	111.7	114	25.0	135.	136.0	140.0	0.71	132.80	1-02	48.7
41	278	1605-	1, 23650	4	27.4	120.4	125	26.5	52.0	54.0	57.0	1.39	45.54	2.27	48.7
42	278		R, 22/85 Ry 13670	4	27.4		158	Position .	Plot or	1	*				48.7
43	278	1616-	R, 19435 Rz 16675	4	27.4	101.2	107	Position	Plot.	fs	pike	- See Ap	pendix O.		48.7
44	278		1 18000	4	27.4	_	126	Sand	1.42		*				48.7

* No shadow observed on sonargram. No height computation

SIDE SCAN TARGET ABSTRACT

OPR- B660-Ruffle-83 RIH 20-13-83

ITEM #

· · · · · · · · · · · · · · ·

SHIP

J.D. TOWFISH HEIGHT RANGE WIDTH CHARTED HEIGHT LENGTH TARGET J.D. OF TARGET OF TARGET OF TARGET LAYBACK OF FISH R2 R3 R4 DEPTH OF TOW DEPTH FIX TOW NUMBER TIME COMPUTED (M) (M/FT) R1 (M) (M) (M) (M/FT) (FT) SPEED (M) (FT) RATES UCT 27.4 101.2 99 Pasition Plat of Spike - See Appendix O. 1616 R2 16000 4 278 1588- R1 29080 1589 R2 9575 4 278 1615-R, 19960 48.7 48.7

DATE

PAGE / O. 3

OPR-_ *BGGO-RU/HE-83*SHEET *R/H 20-13-83*

SIDE SCAN SONAR TARGET LIST

		LEAS				<u> </u>			
TARGET	CHARTED	-REDUCED	HEIGHT OF	WIDTH OF		FURTHE		TIGATION	
NUMBER	DEPTH (FT)	DEPTH (FT)	TARGET (FT)	TARGET (FT)	POSITION	TYPE	DATE	RESULTS	REMARKS
NOIDER	DEL 11. (11)				\$ 041-10-10.0	1			Height of Torget not 10% of depth
19	132	123.9	8.1	17.1	X 072 - 23 - 05.3	None	·	·	
					0041-11-05.3	ft			Sand waves
2	117	POSITIO	N PLOT	ONLY	1 072-20-14.9				
					0041-11-33.6	- 17			(C- 1 m)
3,8	130	POSITION	PLOT	ONLY	× 072-18-57.6				Sand waves
	/ - /	, <u> </u>	, , , , , , , , , , , , , , , , , , , ,		A 041-08-25.4	b •			Height of Target not 10% of depth
4,6	96	·		22.7	1 072-29-14.9				
7,0				-	b 041-10-19.1	11 11			North end of boulder field
5	132			47.4	× 072-23-15.7				
	702				0041-10-11.2				Hotel of Torget not 10% of depth
7a	132	123.7	8.3	4.3	2072-23-14.8			V ALC S	
	700	123.7			0041-09-48.6	4 %			· · · · · · · · · · · · · · · · · · ·
999	125	114.7	10.3	7.0	\$ 072-22-54.0				
1 /9	/20	//4./		,	6041-09-52-6	10 4			
4/0	141		_	11.5	1 072-22-36,3				
10	1.504			77.3	8041-09-53.9			7	Recommend clearance by wire drag
119,386	114	104.8	9.2	3.6	× 072-22-23.8				along with adjacent boulder field
114,000		104. 6	1	3/4	b 041-11-10.1	· *		414	Boulder Field
12	104		٠ ال		× 072- 18-57.8			0,	
16	104	POSITION	PLIT	ONLY		w 1,	1		Sand Wave; Not 10% of
13	117	115.5	1.5	34.8	0041-11-02.1			Pro Marine	
	'''	11513	1.3	37. 6	× 072-30-14.8	4	*		Height of Torget not 102 of
14	122	106.6	5.5.	16.3	8 041-10-42.8				depth
17		706.6	9,0,	7030	X 072-20-49.5	4 %			
159	132	120 1	2.9	6.9	9.041-10-01.2				
154	102	129.1	2./	9./	X 072-22-54,6	 	 		
156	132	126.6	5.4	5.9	8 041-10- 05.1		-	1.	
150	752	126.5	3.7	3,/	1 072 - 22 - 58.6	1	+	 	
150	132	1366	5.4	6.7	Q 041-10-01.5			į.	
150	1 102	126.6	3.7	/	X 072-22-58.3		 	 	
11/-	101-			5,6	0041-09-57.8			1	
16a.	125	120.2	4.8	-,6	1022-23-06.0	1	1	 	7 115 #2727
.7.	125	1,20,00	1	3.7	8 041-09-52,4	1	.∤	-	The state of the s
174	1 /25	120.5	4.5-	3./	1 072-23-12.6	5 1			<u> </u>

PAGE 2. OF 3

OPR-<u>BGGO-Ru/He</u>-83 . SHEET <u>R/H 20+3-83</u>

SIDE SCAN SONAR TARGET LIST

			LEAST							
	TARGET	CHARTED	REDUCED	HEIGHT OF	WIDTH OF				STIGATION	REMARKS
	NUMBER	DEPTH (FT)	DEPTH (FT)	TARGET (FT)	TARGET (FT)	POSITION	TYPE WIRE -	DATE	RESULTS Cleared to 75'	
	18,24	126	116.3	9.7	5.3	\$ 041-09-17.9 \$ 072-25-03.2		TO 236	in one direction	AWOIS #2729
	19	1/3	<u>-</u>		51.2	\$ 041-08-47.9 \$ 072-26-54.0	None		Appears to be	Height of Target not 10% of depth
	20	111	_	-	30.3	\$ 041- 08-41.4 \$ 072-27-15.0			sandwave/ridge	
	21	108	107.0	1.0	3.3	\$ 041-07-55,3 \$ 072-29-14.1	6			11 " "
	22	96			3.3	0041-08-03.4	. "			
	23	119	Position	V PLOT	ONLY	\$ 041-08-59.3 \$ 072-25-59.6	• "			Sand wave ; Not 10 % of depth
1	250	125	119.2	4.8	1.7	& 041-09-52.4 \$ 072-23-00.0	**			Height of Target not 10% of depth
1-46	26a	141	140.1	0.9	3.3	\$041-09-57.3 \$072-22-35/	. "			We state of the st
	27	117	105.7	-	- M	8041-10-47.8 2072-20-14.6	. "			Prior Survey H-9181 Depth 112"
	28	117	109.7	., -	124	\$ 041-10-49.3 \$ 072-20-10,2				" "/12"
	29	117	102.7	_		& 041-11-00.0 \$ 072-19-37.5				107'
	30	104	111.2	_	-	à 041-11-05.8 à 072-19-18.8	•			" "110'
	31	130	112.7	(i) -	辛	\$ 041-11-26.0 \$ 672-18-18.6	" "			" "/22"
	3/9	130	111.2	- 1	_	\$04/-11-21,4 \$072-18-31.2	" "			" "121"
	32	90	86.5	3.3	3.4	\$ 041-11-11.0 \$ 072-18-15.7				Height of Target not 10% of depth
	33	85	96.7	_	-	\$ 041-10-35.8 \$ 072-19-51.9				Prior Survey H-9181 Depth 106
1	34	114	110.7	3,3	3.4	\$ 041-10-03.5 \$ 072-21-35.5				Height of Target not 10% of depth

OPR-<u>BGGO-Pu/Ke</u>-83 SHEET <u>R/H 20-13-13</u>

SIDE SCAN SONAR TARGET LIST

			_		2105	SCAN SONAR TARGE	71 F191			
			LEAST.							
	TARGET	CHARTED	REDUCED	HEIGHT OF	WIDTH OF		FURTHE	R INVES	TIGATION	
	NUMBER	DEPTH (FT)	DEPTH (FT)	TARGET (FT)	TARGET (FT)	POSITION	TYPE	DATE	RESULTS	REMARKS
:	35	114		_	3.3	\$041-10-08.3 \$ 072-21-43.7	None			Height of Target not 10% of depth
i	36	114	109.9	4.1	ه. ه	\$ 041-10-01.7 \$ 072-21-46.1	"			
İ	37	114-	102.4	11.6	10.3	\$ 041-09-52.4 \$ 072-22-17.7	•			Recommend clearance by wire drag along with adjacent boulder field
	3846	114	104.8	9.2	3.6	2041-09-50.4 2072-22-26.2				Recommend clearance by wire drag along with adjacent boulder field
;; 	39 a	114	101.9	16.4	18.6	x 041-09-45.6 x 072-22-39 /	0,		en de la companya de	Height of Target not 10% of depth
1	40	114	111.7	ی, رو	ۍ, ع	& 041-09-39.0 > 072-22-39.0	•			•
A	41	125	120.4	4.6	7.4	& 041-09-41.2 λ 072-22-48.7				
-4/	42	158	Position	Plot a	4	0041-09-21.3 2072-24-00.8				
1	43	107	101.2	_	<u>-</u>	\$ 041-08-27.6 \$ 072-26-32.2				Prior Sarvey H- 981 Depth 129'
	44	126	Pasition F	lot Only		A 041-07-53.4 A 072-28-04.0				Sandanies
	45-	99	101.2	2 1 1 1 1 2 1 2 1 2 1 2 1 2 1 2 1 2 1 2		\$ 041-08-38.) \$ 072-26-01.8	~ ~			Prior Survey 4.9181 Ocpth 106
					,					
			4 P					-		
1						·			·	
		•								

APPENDIX O.

SOUNDINGS APPLIED TO SMOOTH, SHEET

None of the following sounding were plotted on the final field sheet or could be found plotted on any other of the boatshoets supplied.

-							1		•
	JD	Fix #'s	Time UTC	Analog Depth (ft)	Oratt, Settlement + Squat Corr. of +7.2 feet applied	Predicted Tide Corrector (f+)	Reduced Oepth (ft)	Plotted Depth (fr)	Target Number
•	2.78	1583-1584	195345	97.0	105.2	+0.5	105.7	105	27
	278	1584-1585	1954/8	102.0	109.2	+0.5	109.7	109	18
		1585-1586	195810	95.0	102.2	+0.5	102.7	102	29
•		1586-1587	200015	93.5	110.7	+0.5	111.2	///	30
		1588-1589	200805	105.0	112.2	+0.5	112.7	112	31
_	278	1596-1597	2/0300	89.0	96.2	+0.5	96.7	96	33
_	278	1616-1617	220500	94.0	101.2	+0.0	101.2	101	43
	278	1615-1616	220040	94.0	101.2	+0.0	101.2	101	45
	278	1588-1589	200510	103.5	110.7	+0.5	111.2	///	3/@
			<u> </u>				 		
			:		1.		*		
.*		:			· · · · · · · · · · · · · · · · · · ·				
					1		-		
			-	•					
				•		 			
			<u> </u>						
						 			
				 					
			-			·			
•	,		•						
						-	<u> </u>		
						+			
					A-54				

U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION NATIONAL OCEAN SERVICE

TIDE NOTE FOR HYDROGRAPHIC SHEET

Marine Center: Atlantic

OPR: B660

HYDROGRAPHIC SHEET: FE-257 (R/H-20-11-83)

Locality: Long Island Sound

Time Period: August 24 - 25, 1983

Tide Station Used: 876-7150 Bridgeport, Connecticut

Plane Of Reference (Mean Lower Low Water): 2.05 Ft.

Height Of Mean High Water Above Plane Of Reference: 6.8 Ft.

Remarks: Recommended Zoning:

Apply a -25 minute time correction and x0.61 range ratio

Chief, Tidal Datum Section

U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION March 26, 1984 NATIONAL OCEAN SERVICE

TIDE NOTE FOR HYDROGRAPHIC SHEET

Marine Center: Atlantic

OPR: B660

HYDROGRAPHIC SHEET: R/H 20-13-83

Locality: Long Island Sound

Time Period: September 15 - October 5, 1983

Tide Station Used: 846-7150 Bridgeport, Connecticut

Plane Of Reference (Mean Lower Low Water): 2.05 Ft.

Height Of Mean High Water Above Plane Of Reference: 6.8 Ft.

Remarks: Recommended Zoning:

Apply a -25 minute time correction and x0.61 range ratio

Chief, Tidal Datum Section

DATE: 12/19/84

U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION NATIONAL OCEAN SERVICE

TIDE NOTE FOR HYDROGRAPHIC SHEET

Marine Center: Atlantic

OPR: B660

Hydrographic Sheet: R/H 20-13-84

Locality: Long Island Sound

Time Period: October 25, 1984

Tide Station Used: 846-7150 Bridgeport, CT

Plane of Reference (Mean Lower Low Water): 2.05 ft

Height of Mean High Water Above Plane of Reference: 6.8 ft

Remarks: Recommended Zoning:

For AWOIS Item #2729 apply-25*minute time correction and x 0.61 range ratio

to all heights.

* Corrected by telephone conversation (May 1, 1985) with Mr. Joe Mullins, Tidal Datum Section, N/OMA 123.

Chief, Tidal Datums Section

NOAA FORM 76-155 (11-72)										
GE	OGRAPH	IIC NAM	ES				F	E-257 \	WD	
			SK.	JET .	GLE ,	/		1,6	/ ,	
Name on Survey		CHART HO	REVOUS 2	URVEY CORP	Med Ocal TI	LOCAL MA	2.0. GUIDE	OR MAP	S. Lieur L	,51
	. / 6	A CHAR	REV. OH	S.S. WAPS	ON CORMA	LOCK /	3.0.63	HOYLAS V	9.46	
		<u> </u>	<u>_ c</u>	<u> </u>	<u>/ E</u>	<u> </u>	G	/ н	<u> </u>	
LONG ISLAND SOUND (to				,						1
NEW YORK (title)	/									2
SIXMILE REEF (title)	· /									3
									ļ	4
		·								5
										6
										7
										8
										9
										10
			,							11
										12
										13
										14
										15
										16
										17
				Аррі	oved:		,			18
										19
				Ö	Geogr	E 7,	rovvi	inda	b	20
				Chle	f-Geogr	apher	- N/C	42×5		21
					MA. I	R ====				22
		,								23
	-				<u> </u>					24
					 					25
		i .	L	l .	L	1		L	i	

NOAA FORM 61-29 U. S. DEPARTMENT OF COMMERCE	REFERENCE NO.
(12-71) NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION	
	MOR 23 - 76 - 85
I STIED TO ANGMITTING DATA	DATA AS LISTED BELOW WERE FORWARDED TO YOU BY (Check):
LETTER TRANSMITTING DATA	
	ORDINARY MAIL AIR MAIL
το: Γ	REGISTERED MAIL EXPRESS
CHIEF, DATA CONTROL SECTION	GBL (Give number)
HYDROGRAPHIC SURVEYS BRANCH, N/CG243	
NATIONAL OCEAN SERVICE, NOAA BOCKVILLE, MD 20852	DATE FORWARDED
L -	July 8, 1985 NUMBER OF PACKAGES
	Two (2)
NOTE: A separate transmittal letter is to be used for each type of de etc. State the number of packages and include an executed copy of the tion the original and one copy of the letter should be sent under se receipt. This form should not be used for correspondence or transmitted	parate cover. The copy will be returned as a
FE-257 WD R/H-20-11-83 \$ R/H-20-13-83/84	OPR- B660- R4/HZ-83/84
New York, Long Island Sound, Southeast of	Sixmile Reef
Package # 1 of 2 (Tube)	h. C. Dly 20 11-83 and
M-Original Descriptive Report containing report R/H-20-13-83/84 with one Smooth Wire I Smooth Wire Drag Position Overlay included. Note that Control Overlays.	Stor Riff-20-11-03 and
2/4-20-13-83/84 with one Small wire I	rag 1170 Sheel and the
2 - Horizontal Control Overlays.	
	contacts and coverage.
12- Preliminary Field Sheets. 12- Field Wire Drag Strip Plats.	
14 - Office verified Wire Drag Strip Plots.	
$1 \cdot 0 \cdot 1 \cdot \dots \neq 0 \cdot 1 \cdot 2 \cdot 1 \cdot 2 \cdot 1 \cdot \dots = 1 \cdot 1 \cdot 1 \cdot 1 \cdot 1 \cdot 1 \cdot \dots = 1 \cdot 1 \cdot 1 \cdot 1 \cdot 1 \cdot 1 \cdot \dots = 1 \cdot 1 \cdot 1 \cdot 1 \cdot 1 \cdot 1 \cdot \dots = 1 \cdot 1 \cdot 1 \cdot 1 \cdot 1 \cdot 1 \cdot \dots = 1 \cdot 1 \cdot 1 \cdot 1 \cdot 1 \cdot \dots = 1 \cdot 1 \cdot 1 \cdot 1 \cdot 1 \cdot \dots = $	
2- Accordian Folders containing echograms a	nd field data printants.
1 - Envelope containing Side-Scan Smargrar 1 - Envelope containing Smooth Tide Data a 1 - Envelope containing Smooth Tide Data a 1 - Envelope containing data removed from the (R/H-20-11-83 and R/H-20-13-83/84)	is.
1 - Envelope containing Smooth Tide Data a	nd Printouts.
1 - Envelope containing data removed from the	e Descriptive Report
(R/H-Z0-11-83 and R/H-Z0-13-83/84)	•
	·
FROM: (Signature) 2M R 7/:/ II	RECEIVED THE ABOVE
	(Name, Division, Date)
X LCDR David B. Mac Forland, Jr.	H. Durage & Clark
Let LCDR David B. Mac Forland, Jr. Return receipted copy to:	Nucley S. Cruck
	fuly 17, 1985 NICG 243
ATLANTIC MARINE CENTER	11100043
HYDROGRAPHIC SURVEYS BRANCH [N/MOA23]	NICGETS
439 W. YORK STREET	
NORFOLK, VIRGINIA 23510	
L	
_	1

HYDROGRAPHIC SURVEY STATISTICS REGISTRY NO.: FE-257 WD

Number of positions		501
Number of soundings		N/A
Number of control stations		12
	TIME-HOURS	DATE COMPLETED
Preprocessing Examination	9	March 5, 1984
Verification of Field Data	4.3	May 8, 1985
Quality Control Checks	-	
Evaluation and Analysis	60	May 29, 1985
Final Inspection	8	May 28, 1985
TOTAL TIME	120	
Marine Center Approval		<u>May 31, 1985</u>

Transmittal letter of survey and survey records will be included in the Descriptive Report to identify the records accompanying the survey.

ATLANTIC MARINE CENTER EVALUATION REPORT

REGISTRY NO.: FE-257 WD FIELD NO.: R/H-20-11-83 & R/H-20-13-83/84

New York, Long Island Sound, Southeast of Sixmile Reef SURVEYED: August 24, 1983 through October 29, 1984

SCALE: 1:20,000 PROJECT NO.: OPR-B660-RU/HE-83 & OPR-B660-RU/HE-84

SOUNDINGS: Raytheon DE-719B CONTROL: Del Norte 520 Fathometer, Raytheon (Range/Range)

DSF-6000N Fathometer, Klein Side-Scan Sonar,

Wire Drag

1. INTRODUCTION

- a. The purpose of this survey is to provide 100% side-scan sonar coverage over a portion of the Northville Industries Corporation oil tanker route and provide wire drag clearances over two known wrecks, AWOIS Items 2729 and 2730. AWOIS Item 2729 is located in Latitude 41°09'19.25"N, Longitude 72°25'04.09"W, originating from prior survey FE-241 WD (1982) and is believed to be the wreck of the THAMES, a 57-foot iron hull tug. AWOIS Item 2730 is located in Latitude 41°10'29.52"N, Longitude 72°25'34.40"W, originating from prior survey FE-241 WD (1982) and is believed to be the wreck of the BARATARIA, a 69-foot steel hull tug.
- b. This survey is a side-scan sonar and wire drag survey. Raytheon 719B Fathometers (1983) and Raytheon DSF-6000N Fathometers (1984) were operated concurrently with side-scan sonar and wire drag but the soundings are of reconnaissance value only as necessary sounding correctors were not determined. No hydrography beyond reconnaissance hydrography was required. No field plots or any data tapes were made for this hydrography.
- c. This survey is a combination of two field sheets (R/H-20-11-83 and R/H-20-13-83/84) covering a common area over a two year period. The two Descriptive Reports are combined under one cover with R/H-20-11-83 first and R/H-20-13-83/84 following. This Evaluation Report covers both Descriptive Reports.

- d. A standard smooth sheet (A & D) and accompanying position overlay was generated for the wire drag portion of this survey and is attached to this report. No smooth plot was generated for the side-scan sonar portion of this survey since the final field sheet adequately displays the lines run and the contacts found. A chart section depicting the area insonified, the boulder field found, the area described as rocky, and the delineation of areas of sand waves by the hydrographer is attached to this report.
 - e. Corrections and notes made by the Evaluator to the Descriptive Reports are denoted in red ink.

2. CONTROL AND SHORELINE

- a. The source of control is adequately discussed in section F. and Appendix D. of the Descriptive Reports.
 - b. There is no shoreline within the limits of this survey.

3. HYDROGRAPHY

The hydrography collected on this survey is of reconnaissance value only.

4. CONDITION OF SURVEY

The final field sheet, survey records, and reports are adequate and conform to the requirements of the <u>Hydrographic Manual</u> and <u>Wire Drag Manual</u> with the following exception:

- a. In general, the Descriptive Reports are well written.
- b. Prior surveys common to the survey area which were identified in the Project Instructions were used for comparisons by the hydrographer. The Project Instructions were deficient in that they did not list or require comparisons with prior survey H-1591 (1883).
- c. Prior survey H-9089 (1969) was used by the hydrographer for comparisons but was not submitted with the survey's field records.
- d. Lift computations and lift and tide applications to field data was not in accordance with the <u>Wire Drag Manual</u>. Lifts were recomputed during verification. Lifts and smooth tides were applied to the verified data in accordance with the <u>Wire Drag Manual</u> during verification.
- e. The calibrations of the position control systems in the 1983 portion of R/H-20-13-83/84 was accomplished by a method not approved by the <u>Hydrographic Manual</u>, section 4.4.3.3. See section G. of the R/H-20-13-83/84 Descriptive Report.
- f. The geographic positions of four signals listed in Appendix D. of the Descriptive Reports contained slight discrepancies and were corrected during verification. A complete automated listing of the

survey's Control File is attached to Appendix D. of the Descriptive Reports.

- g. A few contacts were flagged on the sonargrams but were not listed in the Target Abstract. These contacts were in close proximity of other contacts of more prominence. These few contacts are of no consequence but all flagged contacts should be listed and addressed in the Target Abstract.
- h. No least depths on contacts were determined by conventional methods as required by section 7.12.3.1. of both the 1983 and 1984 Project Instructions because the hydrographer determined that no critical features existed except the two AWOIS Items 2729 and 2730. AWOIS Item 2729 was resolved by wire drag clearances in opposing directions. AWOIS Item 2730 was cleared by wire drag in one direction only. These two items are further addressed section 7. of this report.

5. JUNCTIONS

Adequate junctions exist with H-10162 WD (1983-84) to the west and FE-268 WD (1983-84) to the east. Adequate side-scan sonar overlap exists between the present survey and the two junctional surveys. Both junctional surveys contain wire drag that is common to the junctional areas of the present survey and provide clearance over some of the present survey's side-scan sonar contacts. The wire drag of both junctional surveys H-10162 WD and FE-268 WD do not junction with the wire drag accomplished on the present survey. No contemporary surveys exist to the north or south of the present survey.

6. COMPARISON WITH PRIOR SURVEYS

a. Hydrographic Surveys

H-1591 (1883) 1:40,000 H-9089 (1969) 1:20,000 (unverified, category 2 survey) H-9181 (1970) 1:20,000

Prior survey H-9181 (1970) covers approximately 75% of the area covered by present side-scan sonar data and all of the present wire drag data. No conflict exist between prior hydrography and present wire drag effective depths. Adequate comparisons between prior hydrography and present reconnaissance hydrography are made by the hydrographer in section K. of the Descriptive Reports. Side-scan sonar contacts within the common area range from 0 to 28 feet shoaler than prior soundings. Only two contacts have computed least depths shoaler than 100 feet (contact 32 with a computed least depth of 86 feet and contact 33 with a computed least depth of 96 feet). Both contacts 32 and 33 are south of the southern edge of the corridor limit. Many of the side-scan sonar contacts are of hydrographic interest but are not a danger to surface navigation. The corridor project depth is 70 feet. None of the side-scan sonar contacts except AWOIS Item 2729 warrants charting. See section 7. a. of this report for charting recommendations on AWOIS Items 2729 and 2730.

Prior survey H-9089 (1969) is an unverified category 2 survey which covers approximately 25% of the area covered by side-scan sonar by the present survey. No present wire drag data is common to this prior survey. This prior survey is a junctional survey with the previously discussed prior survey H-9181 (1970) and combined cover 100% of the present survey. Adequate comparisons between prior hydrography and present reconnaissance hydrography are made by the hydrographer in section K. of the Descriptive Reports. Four side-scan sonar contacts; 4 and 6 (same contact), 20, 21, and 22, are common to this prior survey and all four contacts have a least depth greater than 100 feet and are therefore not a danger to surface navigation and do not warrant charting.

Prior survey 1591 (1883) covers approximately the western two-thirds of the present survey. Prior survey H-9181 (1970) supersedes this prior survey within its common area. Only the area of this prior not superseded by H-9181 was considered in comparison with the present survey. The remaining area is the same area as covered by prior survey H-9089 (1969). The hydrographer did not make any comparison with this prior survey as it was not available as noted in section 4. of this report. Therefore, no comparison between prior hydrography and present reconnaissance hydrography was accomplished as no field plots or data tapes of the present reconnaissance hydrography was included with the field records. The same four side-scan sonar contacts as noted in the comparison for H-9089 are common to this portion of the prior survey and the comparison made above for H-9089 is applicable for this prior survey.

The present survey is adequate only to supplement prior data. It was not the intent of the present survey to supersede prior hydrography.

b. Wire Drag Survey FE-241 WD (1982) - unverified

This prior survey is common to a portion of the present survey by investigating AWOIS Items 1813 (Latitude 41°10'00"N, Longitude 72°26'00"W, P.A.) and 1814 (Latitude 41°10'00"N, Longitude 72°28'00"W, P.A.) by a one nautical mile radius circle of search centered on each position and investigated by 100% coverage side-scan sonar. Two wrecks were located by this prior survey during search for Item 1813. These two wrecks were entered into the AWOIS system as Items 2729 and 2730. No wrecks or obstructions were found during the search for Item 1814. The two wrecks found were assumed to be the two wrecks sought and the hydrographer recommended that the AWOIS Items 1813 and 1814 be deleted from the charts and the two wrecks located be charted as non-dangerous sunken wrecks. No wire drag or diver investigations were conducted on these wrecks. The 1984 editions of charts 12354 and 12358 reflect this change. Although the hydrographer's recommendations appear reasonable, insufficient work was accomplished for disproval of AWOIS Items 1813 and 1814. No charting recommendations pertaining to these two items are made in this report. Charting recommendations for Items 1813 and 1814 will be addressed when this prior survey is processed.

7. COMPARISON WITH CHARTS

12354, 25th Edition, July 31, 1982 12354, 26th Edition, February 4, 1984 12358, 14th Edition, July 10, 1982 12358, 15th Edition, December 1, 1984 a. Hydrography

The charted hydrography originates with the previously discussed prior surveys. The previously discussed prior surveys require no further consideration. The hydrographer makes adequate chart comparisons in section L. of the Descriptive Reports. Additional charting recommendations are:

1) The charted non-dangerous sunken wreck on the 1984 editions of charts 12354 and 12358 designated as AWOIS Item 2729 should remain charted as a non-dangerous sunken wreck and noted as cleared by wire drag to 73 feet. This wreck was cleared in two directions with the greatest clearance depth being 75 feet and the shoalest clearance depth being 73 feet. This wreck lies in approximately 128-foot depths (from H-9181) and extends approximately 10 feet off the bottom giving a side-scan sonar computed least depth of 118 feet. See addingum for charling recommendation

The charted non-dangerous sunken wreck on the 1984 editions of charts 12354 and 12358 designated as AWOIS Item 2730 should remain charted as a non-dangerous sunken wreck. This wreck was cleared by wire drag to 79 feet in one direction only. However, since this lies in approximately 131-foot depths and extends approximately 8 feet off the bottom giving a side-scan sonar computed least depth of 123 feet, it is reasonable to note on the chart the 79-foot wire drag clearance depth. See addendum for

sharting recommendation

b. Aids to Navigation

Aids to navigation common to the surveyed area are adequately discussed in section L. of the R/H-20-13-83/84 Descriptive Report.

8. COMPLIANCE WITH INSTRUCTIONS

This survey adequately complies with the Project Instructions except as noted in the Descriptive Reports and this report.

ADDITIONAL FIELD WORK

This is a good side-scan sonar survey which serves its intended purpose. This is a good wire drag survey for AWOIS Item 2729 and adequately resolves this item. AWOIS Item 2730 was cleared in only one direction and it is desirable to obtain additional clearance in the opposite direction at an opportune time.

MISCELLANEOUS

a. The wire drag data smooth plotted and attached to this report was smooth plotted at the 1:40,000 scale to facilitate the inclusion of the smooth plots in this report on $8\frac{1}{2}$ " by 11" mylar sheets. This is

consistent with section 7.10. of the Project Instructions dated April 12, 1984.

b. No splits exist in the areas of the two wrecks cleared by wire drag.

Maurice B. Hickson, III

Cartographer

Evaluation and Analysis

INSPECTION REPORT FE-257 WD

The completed survey has been inspected with regards to survey coverage, investigation of hangs and clearance depths, cartographic symbolization, and the verification or disproval of charted data. The side scan sonar data have been inspected to gain insight into its overall completeness regarding survey coverage, presentation of survey results, and the verification or disproval of charted data.

The survey, except as noted in the Evaluation Report, is considered completed and adequate to meet National Ocean Service standards. The survey records comply with NOS requirements except as noted in the Evaluation Report. Processing is considered complete.

Inspected

R. D. Sanocki

Chief, Hydrographic Surveys

Processing Section

Hydrographic Surveys Branch

David B. MacFarland, Jr., LCDR, NOAA Chief, Hydrographic Surveys Branch

Approved May 31, 1985

Wesley V. Hull, RADM, NOAA

Director, Atlantic Marine Center



UNITED STATES DEPARTMENT OF COMMERCE National Oceanic and Atmospheric Administration

NATIONAL OCEAN SERVICE
OFFICE OF CHARTING AND GEODETIC SERVICES
ROCKVILLE, MARYLAND 20852

NOV 24 1989

Rip

MEMORANDUM FOR: Commander Russell C. Arnold, NOAA

Chief, Hydrographic Surveys Branch

FROM: Lieutenant Commander Maureen R. Kenny, NOAA

Chief, Operations Section Hydrographic Surveys Branch

SUBJECT: Addendum to Evaluation Report for

FE-257WD (1983-84)

The charting recommendations for AWOIS items 2729 and 2730 were reviewed during the AWOIS update of FE-257WD (1983-84). These two nondangerous sunken wrecks were investigated during this survey using both wire drag and side scan sonar. However, the wire drag survey requirements were erroneously assigned. The clearance depths of 73 and 79 feet which were acquired are misleading; these depths approximate the ships' maximum wire drag depth capability and have no relation to a typical wire drag hang/clearance scenario. Side scan sonar evidence indicates that these wrecks would have been "hung" at approximately 120 feet had the ships had the capability to drag that deep and that they would have been cleared at some depth approximately 2 feet shoaler.


It is recommended that the presently charted wreck symbol and note be deleted, and that the computed least depths from side scan sonar be charted as follows:


Geographic	Currently Charted	Charting	
Position	Note	Recommendations	
41°09'19.25"N, 72°25'04.09"W	Cleared to 73 ft	118 Wk rep 1983	
41°10'29.52"N, 72°25'34.40"W	Cleared to 79 ft	123 Wk rep 1983	


cc:


N/CG22x3 - Danley N/CG244 - Lawrence











MARINE CHART BRANCH RECORD OF APPLICATION TO CHARTS

FILE WITH DESCRIPTIVE REPORT OF SURVEY NO. FE-257WD

INSTRUCTIONS

- A basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart.
- 1. Letter all information.
- 2. In "Remarks" column cross out words that do not apply.
- 3. Give reasons for deviations, if any, from recommendations made under "Comparison with Charts" in the Review.

CHART	DATE	CART	OGRAPHER	REMARKS
10351	6-11-86	4.8	1100	Full Part Before After Marine Center Approval Signed Via
10007	7, 30	//- \$2		Drawing No.56 App'd. corrs.
12358	6-26-91	1- AP	Kones	Full Part Before After Marine Center Approval Signed Via
7 1000	20 77	7. //-		Drawing No. 27 APPhed Cocrections
				Full Part Before After Marine Center Approval Signed Via
				Drawing No.
				Full Part Before After Marine Center Approval Signed Via
				Drawing No.
				Full Part Before After Marine Center Approval Signed Via
				Drawing No.
				Full Part Before After Marine Center Approval Signed Via
				Drawing No.
				Full Part Before After Marine Center Approval Signed Via
				Drawing No.
				Full Part Before After Marine Center Approval Signed Via
				Drawing No.
				Full Part Before After Marine Center Approval Signed Via
				Drawing No.
				Full Part Before After Marine Center Approval Signed Via
				Drawing No.
,				'STD'S CK'd 7-19-85
				Citaj
•	1			